

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	PAGE OF PAGES	
			J	1	1
2. AMENDMENT/MODIFICATION NO. 0002	3. EFFECTIVE DATE 28-Aug-2002	4. REQUISITION/PURCHASE REQ. NO. W807PM-2176-3165		5. PROJECT NO.(If applicable)	
6. ISSUED BY CONSTRUCTION & A/E BRANCH 4155 CLAY STREET VICKSBURG MS 39183-3435	CODE DACW38	7. ADMINISTERED BY (If other than item 6) See Item 6		CODE	
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)			X	9A. AMENDMENT OF SOLICITATION NO. DACW38-02-B-0039	
			X	9B. DATED (SEE ITEM 11) 12-Aug-2002	
				10A. MOD. OF CONTRACT/ORDER NO.	
				10B. DATED (SEE ITEM 13)	
CODE	FACILITY CODE				
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS					
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended.					
Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.					
12. ACCOUNTING AND APPROPRIATION DATA (If required)					
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.					
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.					
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).					
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:					
D. OTHER (Specify type of modification and authority)					
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.					
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) Reference Invitation for Bids (IFB) No. DACW38-02-B-0039 for Flood Control, Mississippi River and Tributaries, Yazoo Basin, Mississippi, Upper Yazoo Projects, Item 5B, Channel Improvement, scheduled to open on 12 September 2002 at 1400 hours. Subject IFB is amended as follows: TECHNICAL SPECIFICATIONS: Section 02052 DEMOLITION: STRUCTURE REMOVAL is reissued in its entirety. Pages revised by this amendment have the notation "Revised by Amendment 0002" at the bottom of the page. Text added by this amendment is underlined. Text deleted by this amendment is shown as overstruck. Encls: Section 02052, pages 1 thru 4					
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.					
15A. NAME AND TITLE OF SIGNER (Type or print)			16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)		
			TEL: _____ EMAIL: _____		
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)		16C. DATE SIGNED 28-Aug-2002	

SECTION TABLE OF CONTENTS

DIVISION 02 - SITE WORK

SECTION 02052

DEMOLITION: STRUCTURE REMOVAL

PART 1 GENERAL

- 1.1 SYSTEM DESCRIPTION
- 1.2 SUBMITTALS
- 1.3 DEMOLITION: STRUCTURE REMOVAL PLAN
- 1.4 PROJECT/SITE CONDITIONS

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

- 3.1 USE OF EXPLOSIVES
- 3.2 DEMOLITION AND REMOVAL WORK
 - 3.2.1 Demolition
 - 3.2.2 Protective Measures
 - 3.2.3 Scrap Metal
- 3.3 DISPOSAL OF REMOVED MATERIALS
 - 3.3.1 General
 - 3.3.2 Removal from Government Property

-- End of Section Table of Contents --

SECTION 02052

DEMOLITION: STRUCTURE REMOVAL

PART 1 GENERAL

1.1 SYSTEM DESCRIPTION

Structure removal consists of demolishing, removing and disposing of the existing bridge near mile 188.5, including the metal swing span, concrete center pivot pier, all spans, piling, all steel truss members, all bridge parts and appurtenances, and east end abutment. Bridge piers shall be cut off and removed as specified in paragraph DEMOLITION AND REMOVAL WORK, subparagraph DEMOLITION.

1.2 SUBMITTALS

Government approval is required for all submittals with a "GA" designation; submittals having an "FIO" designation are for information only. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-08 Statements

Demolition: Structure Removal Plan; FIO Blasting Safety Plan; GA.

The Contractor shall prepare and submit a detailed structure removal plan and a blasting safety plan for acceptance before beginning demolition or removal work.

SD-18 Records

Project/Site Conditions; FIO.

Existing conditions shall be recorded.

1.3 DEMOLITION: STRUCTURE REMOVAL PLAN

The Contractor shall prepare and submit a detailed Demolition: Structure Removal Plan of the work procedures and safety precautions to be used in the demolition, handling, removal, transportation, reclamation or disposal of removed materials. The Contractor shall meet with the Contracting Officer, prior to beginning work to discuss in detail the Demolition: Structure Removal Plan.

1.4 PROJECT/SITE CONDITIONS

Existing project/site conditions shall be recorded with either video equipment or digital photos in the presence of the Contracting Officer showing the condition of structure. Copies of the record shall be submitted and the stated conditions shall be verified before starting work.

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

3.1 USE OF EXPLOSIVES

The Contractor may elect to use explosives for the prosecution of the work. The Contractor shall exercise utmost care not to endanger life and property, including the new work. The Contractor shall be responsible for all damage resulting from the use of explosives. The Contractor shall comply with all laws and ordinances as well as Section 29 "BLASTING" of EM 385-1-1, U.S. Corps of Engineers, SAFETY AND HEALTH REQUIREMENTS MANUAL; Title 29 Code of Federal Regulations Part 1926; and Safety and Health Regulations for Construction (OSHA), with respect to the use, handling, loading, transportation and storage of explosives and blasting agents. A detailed blasting safety plan shall be submitted for approval prior to start of work as a part of the Accident Prevention Plan. This blasting safety plan shall also be submitted for approval to the U.S. Coast Guard at least 45 days before any blasting begins. The office having jurisdiction for these matters is: Commander, 8th Coast Guard District, Bridge Administration Branch, ATTN: John Wachter, Chief, Hale Boggs Federal Building, Room 1313, 501 Magazine St., New Orleans, LA 70130-3396, phone number 504-589-2965. The Contracting Officer must approve this plan prior to transportation of explosives onto the project site..

3.2 DEMOLITION AND REMOVAL WORK

3.2.1 Demolition

The Contractor shall furnish all plant, labor, materials and equipment to satisfactorily demolish and remove the existing bridge and appurtenances, including all bridge parts, as specified herein and shown on the drawings. Piling shall be cut off and removed as specified herein below. All pilings on the left descending bank that are located within the channel enlargement excavation section shall be removed and cutoff at or below the bottom grade of channel enlargement and removed, and as close to channel bottom as possible. Center pivot pier shall be removed at or below the existing channel bottom, below the bottom grade of channel enlargement and as close to channel bottom as possible. Piling on the east abutment shall be cutoff at the enlargement section grade or ground surface whichever is applicable.

All pilings that are located outside the channel enlargement excavation section shall be cutoff at or below the existing ground surface and removed.

3.2.2 Protective Measures

Existing construction shall not be disturbed beyond that indicated unless otherwise approved. Protective measures shall be provided to control accumulation and migration of dust and dirt in all areas of work. Dust, dirt, and debris shall be removed from the areas of work daily.

3.2.3 Scrap Metal

Scrap metal shall become the Contractor's property and shall be removed from the site as it accumulates.

3.3 DISPOSAL OF REMOVED MATERIALS

3.3.1 General

All materials to be removed, including debris, rubbish, scrap, and other non-salvageable materials resulting from removal operations shall be disposed of by removal from the site in accordance with all applicable federal, state and local regulations. The Contractor shall, at his option,

either retain for his own use or dispose of by sale or otherwise, any such material of value. The Government is not responsible for the protection and safe keeping of any materials retained by the Contractor. Materials to be removed shall not be stored on the project site.

3.3.2 Removal from Government Property

The Contractor shall remove the materials from the bridge removal from Government property for disposal. Such disposal shall comply with all Federal, State, and local laws. Such materials shall not be stored on the project site.

-- End of Section --