

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE J	PAGE OF PAGES 1
2. AMENDMENT/MODIFICATION NO. 0002	3. EFFECTIVE DATE 13-Jul-2004	4. REQUISITION/PURCHASE REQ. NO. W807PM-4138-1800	5. PROJECT NO.(If applicable)	
6. ISSUED BY VBURG CONSOL CONTRACTING OFC 4155 CLAY ST VICKSBURG MS 39183-3435	CODE W912EE	7. ADMINISTERED BY (If other than item 6) <b>See Item 6</b>		
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)		X	9A. AMENDMENT OF SOLICITATION NO. W912EE-04-B-0012	
		X	9B. DATED (SEE ITEM 11) 11-Jun-2004	
			10A. MOD. OF CONTRACT/ORDER NO.	
			10B. DATED (SEE ITEM 13)	
CODE	FACILITY CODE			
<b>11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS</b>				
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input checked="" type="checkbox"/> is extended, <input type="checkbox"/> is not extended.				
Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.				
12. ACCOUNTING AND APPROPRIATION DATA (If required)				
<b>13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.</b>				
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.				
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).				
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:				
D. OTHER (Specify type of modification and authority)				
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.				
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) Reference Solicitation No. W912EE-04-B-0012, for FC/MR&T, Section 14, Dillon's Bridge Protection, Bogue Chitto River, Walthall County, Mississippi, heretofore postponed indefinitely, is amended as follows: A new bid opening date of 27 July 2004 at 2:00, is hereby established. Technical Specifications: Section 02272 STONE PAVING is revised and reissued. Pages revised by this amendment have the notation "Revised by Amendment 0002" at the bottom of the page. Text added by this amendment is shown as underlined, and text deleted is shown as overstruck.  Encls: Section 02272, pages 1 thru 4				
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.				
15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)		
		TEL: _____ EMAIL: _____		
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED	
_____ (Signature of person authorized to sign)		BY _____ (Signature of Contracting Officer)	13-Jul-2004	

SECTION TABLE OF CONTENTS

DIVISION 02 - SITE WORK

SECTION 02272

BANK PAVING

PART 1 GENERAL

- 1.1 GENERAL
- 1.2 MEASUREMENT
  - 1.2.1 Stone
- 1.3 PAYMENT
  - 1.3.1 Stone
  - 1.3.2 Stone Stockpile

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

- 3.1 BANK PAVING
  - 3.1.1 Construction Method
  - 3.2.2 Placement
- 3.2 QUALITY CONTROL
  - 3.2.1 General
  - 3.2.2 Reporting

-- End of Section Table of Contents --

## SECTION 02272

### BANK PAVING

#### PART 1 GENERAL

##### 1.1 GENERAL

The work covered by this section consists of furnishing all plant, labor, and stone and performing all work necessary in placing the bank paving complete, as specified herein and shown on the drawings. Stone shall be **Graded Stone "C"** and shall conform to the requirements specified in Section 02540 MATERIALS paragraph STONE.

##### 1.2 MEASUREMENT

###### 1.2.1 Stone

The unit of measurement for stone will be the ton (2,000 pounds) of stone satisfactorily placed in the work. ~~Actual measurement will be in accordance with Section 02495 REINFORCEMENT paragraph MEASUREMENT.~~ When stone is delivered by truck from a quarry or rail road siding, it shall be weighed on approved scales before being placed in the work. Scales will be checked and certified before stone hauling commences and rechecked and recertified whenever variances are suspected and at points when scales have weighed 50,000 ton increments. The Contractor shall furnish the scales and shall weigh the stone in the presence of a Contracting Officer's Representative, who will certify to the correctness thereof. Weight certificates furnished by a public weighmaster will be acceptable in lieu of such procedures when authorized by the Contracting Officer. Unless otherwise approved, public weighmaster scales shall be located within 10 miles of the site of work.

##### 1.3 PAYMENT

###### 1.3.1 Stone

Payment for stone satisfactorily placed in the bank paving will be made at the contract unit price for **"Graded Stone C"**. which price and payment shall constitute full compensation for furnishing all plant, labor, and stone and performing all work necessary in placing the stone in the, bank paving as shown on the drawings.

###### 1.3.2 Stone Stockpile

Stone delivered to the worksite, which requires temporary storage landward of top bank, shall be placed in a container suitable for storing the stone without waste, or a sand-clay-gravel pad may be constructed for the storage area and removed upon completion of the work. If the sand-clay-gravel pad method is used, the pad shall have a minimum thickness of at least [6 inches]. The container or sand-clay-gravel pad method shall be subject to approval prior to delivery of the stone. Upon completion of the work, the storage areas shall be cleaned of all storage residues and returned to their natural condition.

No stone stockpile area is available for this contract. Any Contractor

furnished stone stockpile area(s) shall be approved by the Contracting Officer prior to use. Contractor furnished stone stockpile area(s) shall be in accordance with the guidelines set forth by this paragraph. Storage of stone shall be no closer than 100 linear feet from the closest edge of the stream's top bank. The Contractor's jobsite stockpile shall be maximum of 12 feet high and formed by a series of layers of truckload dumps, where the rock essentially remains where it is placed. Subsequent layers shall be started 10 feet from the edge of the previous layer so that the rock will not roll down the edges of the previous layers. The first layer shall be a maximum of 6 feet high. Any stone which has become contaminated with soil, dirt, or refuse after being stockpiled, will not be put into the work unless the contaminating material has been removed from the stone prior to placement. In areas where stone is stockpiled for placement, the area shall have excess rock removed prior to completion of work. All rock and spalls greater than 3 inches in diameter shall be removed. Where rocks may have become buried due to soft ground or operation of the equipment, the rock shall be disposed of as directed. After the rock has been removed, the storage area shall be graded, dressed, and filled to return the ground surface as near as practical to the condition that existed prior to construction. All restoration cost of Contractor furnished stone stockpile area(s) shall be the sole responsibility of the Contractor.

## PART 2 PRODUCTS (Not Applicable)

## PART 3 EXECUTION

### 3.1 BANK PAVING

#### 3.1.1 Construction Method

The bank paving shall be constructed of **Graded Stone "C"** to the lines, grades, and sections shown or as noted on the drawings. Construction of the bank paving shall commence at the upstream end and continue progressively to the downstream end.

#### 3.2.2 Placement

The stone shall be placed by skip, grapple, hand, or other approved method, in such a manner as to produce a reasonably well graded mass of stone with the minimum practicable percentage of voids. Stone shall not be dropped from a height greater than 3 feet. A variation of 1 foot above or 6 inches below the specified deviation will be allowed provided these variations are gradual over a minimum distance of 10 feet measured along the bank paving. Stone delivered on-site shall be contained as specified in paragraph STONE.

### 3.2 QUALITY CONTROL

#### 3.2.1 General

The Contractor shall establish and maintain quality control for stone construction operations to assure compliance with contract specifications and maintain records of his quality control for all construction operations including, but not limited to, the following:

- a. Bank Paving. Check grade, slope, and placement of stone for compliance with design sections and specifications.

#### 3.2.2 Reporting

Three copies of these records and tests, as well as the records of corrective action taken, shall be furnished the Government daily. The report shall be as prescribed in Section 01451 entitled CONTRACTOR QUALITY CONTROL.

-- End of Section --