

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE J	PAGE OF PAGES 1 1
2. AMENDMENT/MODIFICATION NO. 0002	3. EFFECTIVE DATE 26-Jul-2004	4. REQUISITION/PURCHASE REQ. NO. W807PM-4153-2497	5. PROJECT NO.(If applicable)		
6. ISSUED BY VBURG CONSOL CONTRACTING OFC 4155 CLAY ST VICKSBURG MS 39183-3435		CODE W912EE	7. ADMINISTERED BY (If other than item 6) See Item 6		
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)			<input checked="" type="checkbox"/>	9A. AMENDMENT OF SOLICITATION NO. W912EE-04-B-0015	
			<input checked="" type="checkbox"/>	9B. DATED (SEE ITEM 11) 18-Jun-2004	
				10A. MOD. OF CONTRACT/ORDER NO.	
				10B. DATED (SEE ITEM 13)	
CODE			FACILITY CODE		
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS					
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input checked="" type="checkbox"/> is extended, <input type="checkbox"/> is not extended.					
Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.					
12. ACCOUNTING AND APPROPRIATION DATA (If required)					
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.					
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.					
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).					
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:					
D. OTHER (Specify type of modification and authority)					
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.					
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) Reference Solicitation No. W912EE-04-B-0015 for New Water Well, Sardis Lake, Mississippi, heretofore postponed indefinitely, is amended as follows: <div style="text-align: center;"> BID OPENING DATE A new bid opening date and time of August 05, 2004 at 1400 hrs is hereby established. </div> <div style="text-align: center;"> TECHNICAL SPECIFICATIONS Section 02052 DEMOLITION: STRUCTURE REMOVAL is revised and replaced. </div> Pages revised by this amendment have the notation "Revised by Amendment 0002" at the bottom of the page. Text added by this amendment is shown as underlined. Encls: Section 02052, pages 1 through 4.					
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.					
15A. NAME AND TITLE OF SIGNER (Type or print)			16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)		
15B. CONTRACTOR/OFFEROR			16B. UNITED STATES OF AMERICA		16C. DATE SIGNED
(Signature of person authorized to sign)			BY _____		26-Jul-2004
			(Signature of Contracting Officer)		

SECTION TABLE OF CONTENTS

DIVISION 02 - SITE WORK

SECTION 02052

DEMOLITION: STRUCTURE REMOVAL

PART 1 GENERAL

- 1.1 SYSTEM DESCRIPTION
- 1.2 SUBMITTALS
- 1.3 INTERRUPTION OF SERVICES
- 1.4 DEMOLITION: STRUCTURE REMOVAL PLAN
- 1.5 PROJECT/SITE CONDITIONS

PART 2 PRODUCTS

- 2.1 FILL MATERIAL

PART 3 EXECUTION

- 3.1 PRECAUTION AGAINST MOVEMENT
- 3.2 DEMOLITION AND REMOVAL WORK
 - 3.2.1 Demolition
 - 3.2.1.1 Below-Grade Construction
 - 3.2.2 Protective Measures
 - 3.2.3 Salvageable Materials and Equipment
 - 3.2.4 Scrap Metal
 - 3.2.5 Structures
 - 3.2.6 Mechanical Equipment and Fixtures
- 3.3 DISPOSAL OF REMOVED MATERIALS
 - 3.3.1 General
 - 3.3.2 Burning on Government Property
 - 3.3.3 Removal from Government Property

-- End of Section Table of Contents --

SECTION 02052

DEMOLITION: STRUCTURE REMOVAL

PART 1 GENERAL

1.1 SYSTEM DESCRIPTION

The Contractor shall provide a detailed structure removal plan and schedule so as to remove the existing tank and structure, and have the new tank and structure operational no later than 01 March 2005. The detailed structure removal plan and schedule must provide that interruption of service shall extend no longer than 60 consecutive days. Structure removal shall not begin until the new tank is complete and on site. Structure removal consists of removing the old tank, tank saddles, concrete slab, brick and concrete wall as necessary to install the new tank.

1.2 SUBMITTALS

Government approval is required for all submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Project/Site Conditions

Existing conditions shall be recorded.

Interruption of Services; G

Submit written request for interruption of services.

SD-07 Certificates

Demolition: Structure Removal Plan

The Contractor shall prepare and submit a detailed structure removal plan and schedule for acceptance before beginning demolition or removal work.

1.3 INTERRUPTION OF SERVICES

Written approval shall be obtained at least 48 hours prior to interrupting the following services:

- a. Utility Outages.
- b. Traffic Interruptions.

1.4 DEMOLITION: STRUCTURE REMOVAL PLAN

The Contractor shall prepare and submit a detailed Demolition: Structure Removal Plan of the work procedures and safety precautions to be used in

the identification, excavation, demolition, handling, removal, transportation, reclamation or disposal of removed materials, backfill and erosion control. The Contractor shall meet with the Contracting Officer, prior to beginning work to discuss in detail the Demolition: Structure Removal Plan.

1.5 PROJECT/SITE CONDITIONS

Existing conditions project/site conditions shall be recorded in the presence of the Contracting Officer showing the condition of structures and other facilities adjacent to areas of alteration or removal. Such record shall contain the elevation of the top of foundation walls, the location and extent of cracks and other damage and description of surface conditions that exist prior to the start of work. Copies of the record shall be submitted and the stated conditions shall be verified before starting work.

PART 2 PRODUCTS

2.1 FILL MATERIAL

Fill material shall be as specified in Section 02224 BACKFILL AND EMBANKMENT, paragraph RANDOM FILL AND BACKFILL. In addition, fill material shall be free from roots and other organic matter, trash, debris, frozen materials, and stones larger than 2 inches in any dimension.

PART 3 EXECUTION

3.1 PRECAUTION AGAINST MOVEMENT

The Contractor shall provide shoring and bracing or other supports to prevent movement, settlement, or collapse of facilities adjacent to areas of alteration and removal that are to remain.

3.2 DEMOLITION AND REMOVAL WORK

3.2.1 Demolition

Concrete slabs shall be broken up and removed.

3.2.1.1 Below-Grade Construction

Foundation walls shall be demolished to a depth of not less than 12 inches below the existing ground surface.

3.2.2 Protective Measures

Existing construction shall not be disturbed beyond that indicated or necessary for installation of new work. Temporary shoring and bracing shall be provided for support of building components to prevent settlement or other movement. Protective measures shall be provided to control accumulation and migration of dust and dirt in all areas of work. Dust, dirt, and debris shall be removed from the areas of work daily.

3.2.3 Salvageable Materials and Equipment

The Government will designate materials and equipment to be salvaged. Identification tags shall be provided on items boxed or placed in containers, indicating the type, size, and quantity of materials. Those designated salvaged materials and equipment shall not become the property

of the Contractor, but shall remain the property of the Government.

3.2.4 Scrap Metal

Scrap metal shall become the Contractor's property and shall be removed from the site as it accumulates.

3.2.5 Structures

Removal operations shall be performed on existing structures as required to complete the work.

- a. Existing concrete shall be demolished, removed, and disposed.

3.2.6 Mechanical Equipment and Fixtures

Mechanical hardware shall be disconnected at the nearest convenient connection to existing services that are to remain.

3.3 DISPOSAL OF REMOVED MATERIALS

3.3.1 General

All materials to be removed, including debris, rubbish, scrap, and other non-salvageable materials resulting from removal operations shall be disposed of by removal from the site in accordance with all applicable federal, state and local regulations. Materials to be removed shall not be stored on the project site.

3.3.2 Burning on Government Property

Burning of materials removed from demolished structures will not be permitted on Government property.

3.3.3 Removal from Government Property

Waste materials removed from demolished structures shall be transported from Government property for disposal.

-- End of Section --